© 2007 COX ENGINEERING DBA CAMBRIDGEPORT AIR SYSTEMS.
THE INFORMATION CONTAINED IN THIS DOCUMENT IS PROPRIETARY TO
COX ENGINEERING COMPANY DBA CAMBRIDGEPORT AIR SYSTEMS.
THIS DOCUMENT OR THE INFORMATION CONTAINED IN WHOLE OR IN PART
MAY NOT BE ISSUED TO ANOTHER PARTY WITHOUT WRITTEN CONSENT AND
AUTHORIZATION FROM CAMBRIDGEPORT. TRANE YCD036C **ROOF CURB** 1000030 SUBMITTAL Approval Block Drawn Date: 12/28/22 Rev. A Date: _____ Company: _____ Drawn By: PRG Estimated Weight: 103 LBS. Job Name: _____ Approved By: Notes: 32 5/8" **−** 15 1/4" - 12 11/16" 33 3/16" SA INSULATED INSULATED 39 7/16" RA PANEL PANEL INSULATED 73 5/8" **GASKET** (BY C.A.S.) COUNTER **FLASHING** 1 X 4 **WOOD NAILER** (FIELD SUPPLIED) (BY C.A.S.)~ ROOFING FELT (FIELD SUPPLIED) **DETAIL A** RIGID INSULATION (FIELD SUPPLIED)~ FEATURES: CANT STRIP Cambridgeport (FIELD SUPPLIED) Mitered Corners. Gasketing Provided for Unit to Curb Sealing.
Roof Curb is Fabricated of Heavy Gauge Galvanized Steel.
Full Perimeter Wood Nailer.
Pre-Punched Holes and Hardware Included for Curb Assembly.
Roof Curb is Shipped Knocked Down.
Roof Curb is Labeled with RTU # if Applicable. 2. 3. SECTION E-E TYPICAL INSTALLED 4. 4 Carleton Drive 5. **CURB SECTION** 1-800-648-2872 6. 7. Georgetown MA 01833 **HVAC Accessories & Engineered Systems**